



गौरीगङ्गा नगरपालिका नगरकार्यपालिकाको कार्यालय

चौमाला, कैलाली
सुदूरपश्चिम प्रदेश

फोन नं ४१८०५९-०९१ : , ४१८०६०
वेबसाइट: www.gaurigangamun.gov.np
ई : -info.gaurigangamun@gmail.com

पत्र संख्या : ०८२/०८३

चलानी नं. :

श्री सरोकारवाला सवै ।



मिति:- २०८३/२/२२

विषय:- Estimate प्रयोजनका लागि दर रेट पेश गर्ने सम्बन्धमा ।

चौमाला बहुमुखी क्याम्पसको लागि आवश्यक फर्निचर सामग्री खरिद गर्नुपर्ने भएकोले Estimate प्रयोजनका लागि दर रेट पेश गर्न इच्छुक फर्म, सप्लायर्स तथा व्यवसायीहरूबाट यो सूचना प्रकाशित गरिएको छ। इच्छुक इजाजतप्राप्त फर्म/कम्पनीहरूले सूचना प्रकाशित भएको मितिले ३ (तीन) दिनभित्र संलग्न BOQ मा आफ्नो दररेट सिलबन्दी वा इमेलमार्फत पेश गर्नुहुन अनुरोध छ।


पुनर्म रेग्मी
शाखा अधिकृत
अधिकृत सातौं

गौरीगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल



BOQ

योजनाको नाम:- चौमाला बहुमुखी क्याम्पसका लागि फर्निचर खरीद
स्थान:- गौरीगङ्गा नगरपालिका-१ कैलाली

S.N.	Description	Unit	Quantity	Rate in figure NRs.	Rate in Words	Amount NRs.	Remarks
1	Supplying, fixing, and installing wall racks of overall size 11'-0" x 7'-6", made with 10 mm thick plywood laminated on one side for the wall-facing surface and 16 mm thick plywood laminated on both sides for partition boxes of sizes 22" x 14", 22" x 12", 22" x 10", and 22" x 8", including fitting of 5 mm thick white sliding glass shutters with all necessary accessories such as channels, handles, locks, magnets, and all other required hardware, complete in all respects as per the approval and direction of the Site Engineer.	set	1.0				
2	Supplying, fixing, and installing counter of overall size 7'-0" x 2'-0" x 2'-5", made with 19 mm thick plywood for the main structure and 12 mm thick plywood for other portions, using chapra finish for internal surfaces and Formica finish for outer exposed faces, including making 4 partitions with openable doors and providing a glass partition box above the counter of size 7'-0" x 1'-6", complete with hinges, channels, handles, locks, magnets, and all other necessary fittings and hardware, with proper shining/polish finish, complete in all respects as per the approval and direction of the Site Engineer.	set	1.0				
3	Supplying, fixing, and installing counter of overall size 10'-0" x 1'-8" x 2'-5", made with 19 mm thick plywood for the main structure and 12 mm thick plywood for other portions, using chapra finish for internal surfaces and Formica finish for outer exposed faces, including making 4 drawers and 2 keyboard trays, complete with hinges, channels, handles, locks, magnets, and all other necessary fittings and hardware, with proper shining/polish finish, complete in all respects as per the approval and direction of the Site Engineer.	Set	1.0				
4	Supplying, fixing, and installing L-shape counter of overall size 10'-0" x 1'-8" x 2'-5" and 6'-0" x 2'-0" x 2'-5", made with 19 mm thick plywood for the main structure and 12 mm thick plywood for other portions, using chapra finish for internal surfaces and Formica finish for outer exposed faces, including making 4 drawers and 2 keyboard trays, complete with hinges, channels, handles, locks, magnets, and all other necessary fittings and hardware, with proper shining/polish finish, complete in all respects as per the approval and direction of the Site Engineer.	Set	1.0				
Total							
13% Vat							
Grand Total							

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

Phone :

Date :