



गौरीगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय

फोन नं. : ०९१-४१८०५९, ४१८०६०
वेबसाइट: www.gaurigangamun.gov.np
ई-मेल : info.gaurigangamun@gmail.com

प.सं.: २०८२/०८३

च.नं.:

चौमाला कैलाली
चौमाला, कैलाली
प्रदेश, नेपाल
२०७३

मिति: २०८२/०९/११

विषय: दररेट पेश गर्ने सूचना ।
(दोस्रो पटक प्रकाशित मिति: २०८२/०९/११)

यस कार्यालयको देहाय कार्य शिलबन्दी दरभाउपत्र माफत सम्पन्न गर्नुपर्ने भएको हुँदा ईच्छुक व्यक्ति/फर्म वा कम्पनी बाट ७ (सात) दिन भित्र दररेट पेश गर्न आव्हान गरिएको छ ।

सि.न.	विवरण	जम्मारकम (मु.अ.कर सहित) रु.	BOQ खरिद गरि पेश गर्ने अन्तिम मिति र समय
१.	प्रथमिक स्वास्थ्य केन्द्र चौमाला प्रयोगशाला मर्मत	रु.२,४७,४२७.२१/- (दुई लाख सरचालिस हजार चार सय सत्ताइस पैसा एक्काइस मात्र)	२०८२/०९/१७ गते कार्यालय समय भित्र
२.	वडा नं. ७ को भागीराम टमट्टाको घर देखि मन्त्री टोल सडक स्तरोन्नती (पानी पिच)	४,९९,५०७.०३/- (चार लाख उनानसय हजार पाँच सय सात पैसा तीन मात्र)	२०८२/०९/१७ गते कार्यालय समय भित्र

पालना गर्नुपर्ने शर्त तथा पेश गर्नु पर्ने कागजात:-

१. दर्ता भएको ईजाजत प्राप्त निर्माण व्यवसायी/सप्लायर्स भए ईजाजत नविकरण भएको प्रमाण पत्र, मु.अ.कर दर्ता, आ.व. २०८१/०८२ को कर चुक्ता प्रमाण पत्रको प्रतिलिपि,
२. BOQ यस कार्यालय बाट रु.१००० (एक हजार) मा खरिद गर्नुपर्नेछ । सो खरिद गरेको सकल रसिद BOQ साथ पेश गर्नुपर्नेछ ।
३. BOQ शिलबन्दी नभएको दरभाउपत्र दर्ता गरिने छैन ।
४. BOQ मा दररेट अंक र अक्षर दुवैमा लेखिएको/ केरमेट नभएको हुनुपर्नेछ ।
५. म्याद नाघि रित नपुगेको दरभाउपत्र मुल्याङ्कनमा समावेश गरिने छैन ।

111V

२०८२/०९/११
हरीश सन्निव
उपसचिव
गौरीगङ्गा नगरपालिका



Gauriganga Municipality
Office of Municipal Executive
Chaumala, Kailali
Bill of Quantities

Name of project :- प्राथमिक स्वास्थ्य केन्द्र चौमाला प्रयोगशाला मर्मत
Location :- नौगंगा -०२, कैलाली

SN	Description of Works	Unit	Quantity	Rate (Nrs)		Total Amount(Nrs)	Remarks
				Rate in Figure	Rate in Words		
1	Dismantling of brick masonry work For Wall as per specification and direction of engineer	m ³	0.48				
2	PCC for RCC: Structural concrete (1:1.5:3 or M20 grade) with cement sand and crushed aggregate in any form, size, shape and level for all reinforced cement concrete including mixing, laying, compacting, curing and finishing excluding centering shuttering and cost of reinforcement all complete	cum	0.41				
3	FORMWORK FOR SHUTTERING: Providing erecting, fixing, striking, removing and clearing, hutting Form Works(Using 19mm ply board) as specified height, for all concrete works including plays, ties, keys wedges, props, nails, bracings, brackets, cutting holes for passing embedment all complete as per instruction of Engineer, drawings and specification.	sq.m	4.08				
4	TOR STEEL WORK: Fixing for steel reinforcement grade 1 conforming to I.S. 1786-1985 in RCC work including cleaning, cutting, bending, placing in position and binding with no.16 swg annealed binding wire all complete.	Kg	55.55				
5	BRICKWORK: First class Chimney made Brickwork in substructure / super structure in (1:6) cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete.	Cum	0.41				
6	PLASTERING WORK: Providing 12.5mm thick cement sand Plaster with 1:6 Cement mortar at all height on walls including chipping and hacking of concrete surface immediately after removal of shuttering, wetting the surfaces, scaffolding, cleaning and curing all materials and labours complete as per instruction of Engineer, drawings and specification.	Sqm.	4.68				
7	TILE WORK: Non Skidding ceramic Tile 300*300 with cement sand mortar of 1:4 ratio on floor including as per instruction of engineer, drawing and specification.	Sqm	13.60				
8	12 mm thick Partition Board one side Laminated for the purpose of Sliding in Separator	Sqm	3.90				
9	Aluminium Partition-Fabrication, Supplying & Fixing Of 100mm Series in Natural Color anodized with necessary hardware. 5mm Al Composite/5mm Clear Glass/8mm Nepal Board Section Size 101x45x1.2mm	Job	6.00				
10	Aluminium DOORS Hinge Fabrication, Natural Color anodized section size 101x45x1mm including Door closer, american Handle, stopper, Aldrop, Lock Rubber, Brush, Gaskets & Necessary Hardware etc.(5mm Al Composite/5mm clear glass/8mm Nepal Board	Sqm	2.00				
11	Aluminium WINDOWS - 2 Pannel Sliding, Natural Colour anodized. Section size 87.4x56x1.2mm. Including Auto Lock, Roller, Brush, S.S. Mosquito Net, 4mm Clear Glass, Knobs, Gaskets & Necessary Hardware etc	Sqm	2.21				
12	MS pipe truss work including cutting, welding, fitting and painting work all complete	Kg	55.35				
13	26 gauge coloured CGI sheet roofing work	Sqm	15.00				
14	Double coat water proof cement paint	Sqm	33.00				
15	light point and power point wiring works Using 3/22 copper wire, wooden list, PVC pipe, plug, switch, ceiling rose, holder, socket round board of Rath, Anchor or equivalent company.	Points	15.00				
16	Wooden Rack For Seating Lab Equipment (1'0.50)	Ls	1.00				
17	Plumbing works including supplying and fitting steel sink(18"22"8) all complete	Ls	1.00				
18	12 W round/ square recessed concealed light fitting works all complete. Ns/Is certified	Nos	6.00				
			Sub Total				
			VAT Amount @13%				
			Grand Total Amount				

On Behalf of Firm
Signature :
Name of Firm:
Seal :
Phone :



गौरिगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल
BILL OF QUANTITY (BOQ)



प्रमाणित
२० चैत्र १९६

योजनाको नाम :- भागीराम टमाटाको घर देखि मन्त्रीटोल सम्म सडक स्तरउन्नति (पानि पिच)
ठेगाना : गौरिगंगा नगरपालिका -०७, कैलाली

SN	Description of Works	Unit	Quantity	Rate (Nrs)		Amount (Nrs)
				Rate in Figure	Rate in Words	
Part 1 : SITE CLEARANCE						
1	Scarifying Existing road Surface to a Depth of 50 mm by Manual Means, Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications	m2	428.50			
Part:2 Construction works:						
2.1	Excavation For Cross Drainage Works in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means	m3	24.00			
2.2	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications	m3	78.60			
Part:3 Pavement works:						
3.1	Providing and laying granular Sub-Base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means	m3	235.68			
Part:4 Provisional works:						
4.1	Off site verification Lab testing of materials as required by the engineer's representative	PS	1.00	5000/-		
4.2	Providing and installation of project signboards with size of 1.2 x 1.0 m as per specification and instruction of engineer [110]	PS	1.00	1500/-		
Total						
Vat @ 13% of Total						
Grand Total						

Note :

- The numbers enclosed in the bracket in the particulars represent DOR Standard Specifications Section Number
- All the specified material acceptance and work compliance tests as per the Standard Specification, 2001 and Quality Assurance Plan (QAP) shall be carried out by the Contractor(s) at his own cost.

On behalf of contractor

Contractor's Signature

Firm

Seal :

Contractor's Name :

Permanent Address

Phone

Date