



प.सं.: २०८०/०८१

च.नं.:

गौरीगङ्गा नगरपालिका  
नगर कार्यपालिकाको कार्यालय  
चौमाला, कैलाली  
सुदूरपश्चिम प्रदेश, नेपाल  
२०७३

फोन नं ४१८०५९-०९९: , ४१८०६०  
वेबसाइट: www.gaurigangamun.gov.np  
ईमेल: info.gaurigangamun@gmail.com

मिति: -२०८१/०२/२२

विषय: दर रेट पेश गर्ने बारे सूचना ।  
(प्रथम पटक प्रकाशित मिति: -२०८१/०२/२२)

श्री सरोकारवाला सबै (यस नगरपालिकाको कार्यालयमा सुचिकृत)

उपरोक्त सम्बन्धमा यस नगरपालिकाको कार्यालय अन्तर्गत तपसिलका कार्य गर्नु पर्ने र सो कार्य दरभाउपत्र (कोटेसन) मार्फत गर्नुपर्ने भएकाले उक्त कामको लागी संलग्न BOQ अनुसार आफुले गर्न सक्ने दररेट भरी यस कार्यालयमा पेश गर्न हुन जानकारी गराईन्छ ।

सि.न.	विवरण	जम्मा रकम (मु.अ.कर) सहित	BOQ खरिद गरि पेश गर्ने अन्तिम मिति र समय	कैफियत
१.	नवीकरणीय उर्जा प्रविधि जडान (सौर्य सडक बत्ती मर्मत)	९९६८०९.२९	२०८१/०२/२८ गते कार्यालय समय भित्र	

पेश गर्नु पर्ने कागजात:-

१. दररेट पेश निर्माण व्यवसायिले अनिवार्य रुपमा दररेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहित नविकरण भएको फर्म / कम्पनि दर्ता प्रमाण पत्रको प्रतिलिपि, नविकरण भएको व्यवसाय दर्ता ( निर्माण व्यवसायि ईजाजत पत्र), प्रमाणपत्र प्रतिलिपि, मु.अ.कर दर्ता प्रमाण प्रतिलिपि र आ.व. २०७९/८० को कर चुक्ता प्रमाण पत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्नेछ ।
२. BOQ यस कार्यालयको वेबसाइटमा <http://www.gaurigangamun.gov.np> बाट डाउनलोड गर्न सकिनेछ । BOQ खरिद कार्य वाफतको रु.१००० (एक हजार) राजस्व शाखबाट बुझाएको नगदी रसिद तिरी अनिवार्य दररेट साथ पेश पेश गर्नुपर्ने छ । BOQ भरि खामबन्दी गरि बाहिरी खाममा फर्मको नाम ठेगाना र ठेका संकेत उल्लेख गरि पेश गर्नुपर्नेछ ।
३. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि खामबन्दी गरी भित्र राखि पेश गर्नुपर्नेछ केरमेट भएको दररेट (BOQ) मुल्याङ्कनमा समावेश गरिने छैन ।
४. दर रेट पेश गर्ने निर्माण व्यवसायीले कार्यालयमा अनिवार्य सुचिकृत गर्नुपर्ने छ । सुचिकृत नभएका निर्माण व्यवसायीलाई मुल्याङ्कनमा समावेश गर्न सकिने छैन ।

  
२०.०२.२२  
धर्म राज विनाडी

प्रमुख प्रशासकीय अधिकृत

**प्रमुख प्रशासकीय अधिकृत**



Name Of Project : Nabikaraniya Urja Prabhidhi Jadan  
Location : Gauriganiga, Kailali

Gauriganiga Municipality  
Office of Municipal Executive  
Kailali  
सुदूरपश्चिम प्रदेश, नेपाल  
गाउँपालिका क्षेत्र, कवलपुर जिल्ला

21.10.2018  
22.10.2018  
23.10.2018

SN	Description of Works	Technical Specification	Unit	Rate (Nrs) Rate in Figure	Rate (Nrs) Rate in Words	Amount	Remarks
<b>A Net Vatable Materials</b>							
1	Charge Controller With Dusk to Down Function, three Stage dimming function (Sensor)	Automatic Dusk to Down MIPPT Charge Controller 15A/20A 12-24V ,three stage dimming function,-5 to +55 °C/35 to 85%RH (Without Condensation) Solar reverse-charging protection, solar reverse-connection protection, battery over charge protection, battery over-discharge protection ,battery reverse-connection protection. RETS Certified.	Set	16.00			
<b>B Vatable Materials</b>							
1	Battery	Battery(12v),100AH Pb4 Battery/82Ahp/C10 Li-Ion(LiFePO4) Battery RETS certified, Minimum 5years Warranty	Set	12.00			
2	Street Light (LED)	LED Street Light 40W, The proposed LED life shall be minimum 50,000 hours, must submit IP65 or above and beam angle should be 120 degree compliance certificate. RETS certified.	Set	20.00			
5	Interconnecting Wire & Other Accessories, (Nut-Bolt Earthing Set)	Installation of Materials( Battery Box,2.5mm2 cable,cable shoe,flexible pipe, nut bolt, connector, PVC tape and other required materials)	lot	22.00			
6	Disemantling And Transportation Of Existing Light	Replacing And Removing Of Existing Street Light Pole And transportation for new Place	LS	8.00			
7	E/W Excavation	Earth work excavation in foundation and trenches in all type of soil except rock in both dry and wet conditions including back filling of excavated material, shoring and strutting whenever necessary, pumping out water from the trenches etc as directed with the lead of 50 m and lift 3m all complete	Cum	2.59			
8	Stone Soling	Providing and laying Dry-stone soling in foundation work including levelling etc. complete. 150 mm stone soling in foundation	Cum	0.43			
9	P.C.C. 1:2:4 Work	Plain cement concre PCC(1:2:4) in foundation, floors etc. with cement, sand and crushed aggregate of 10 mm to 38mm gauge including mixing laying in line & level with curing all type of works complete as per specifications & instructions	Cum	2.30			
						Sub Total	
						Val@ 13 %	
						Total of B	
						Grand Total of (A + B)	

In Words:-

On Behalf of Firm.

Signature :

Name of Firm:

Seal :

Name of Authorized Person:

Permanent Address :

Phone :

Date :