



गौरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली

सुदूरपश्चिम प्रदेश, नेपाल

भौतिक योजना विभाग (BOO)

सुदूरपश्चिम प्रदेश, कैलाली
गौरीगंगा नगरपालिका

सुमाला
२०८०/११/१३

Name Of Project: गौरीगंगा नगरपालिका वार्ड नं. ०१ कायदा नं. १९९
Location: Gauriganga, 07 Kailali
F/Y:- 2080/081

SN	Description of Works	Unit	Quantity	Rate in Figure	Rate (Nrs)	Rate in Words	Amount (Nrs)
Part 1 : SITE CLEARANCE							
1	Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications. Unit = sqm (For 600 sqm, Lead upto 30 m)	m2	800				
Part 2 : CROSS DRAINAGE SIDE DRAINAGE AND MISCELLANEOUS WORK							
2.1	Excavation For Cross Drainage Works in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means.	m3	257.4				
2.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	3.6				
2.3	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	m3	2.4				
2.4	Providing and laying Stone Masonry work in cement mortar 1:6 in structure complete as per Drawing and Technical Specifications Random Rubble Masonry	m3	7.93				
2.5	Humepipe Installation Works 450mm	Nos	5				
2.6	Humepipe Installation Works 300mm	Nos	1				



नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल

BILL OF QUANTITY (BOQ)

Name Of Project: सुदूरपश्चिम प्रदेशको विकास
Location: Gauriganga, 07 Kailali
F/Y:- 2080/081

SN	Description of Works	Unit	Quantity	Rate in Figure	Rate (Nrs)	Rate in Words	Amount (Nrs)
Part 3: PAVEMENT WORKS							
3.1	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means	m3	333				
Part:4 PROVISIONAL SUMS FOR							
4.1	Off site verification Lab testing of materials as required by the engineer's representative	PS	1	5000/-			
4.2	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	PS	1	1000/-			
Total Construction Cost							
Vat @ 13% of Total							
Total Provisional Sum							
Grand Total							

Note:

- * The numbers enclosed in the bracket in the particulars represent DOR Standard Specifications Section Number.
- * All the specified material acceptance and work compliance tests as per the Standard Specification, 2001 and Quality Assurance Plan (QAP) shall be carried out by the Contractor(s) at his own cost.

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

Phone :

Date :