


VMS  
2020/99/25.



योजनाको नाम:- बुद्धि भुसालको घर हुदै लगडी जाने सडक ग्राभेल तथा मर्मत  
ठेगाना : गौरिगंगा नगरपालिका -०४, कैलाली

(BILL OF QUANTITIES)

S.N.	Description	Unit	Quantity	Rates		Amount (Nrs)	Remarks
				In Figure	In Words		
<b>A</b>	<b>General</b>						
i	Providing and installation of project signboards with size of 1.2 x 1.0 m as per specification and instruction of engineer [110]	Ps	1.00	1500.00		1500	
ii	Off site verification Lab testing of materials as required by the engineer's representative	Ps	1.00	5000.00		5000	
					<b>Total</b>	<b>6500</b>	
<b>B</b>	<b>Constructions</b>						
2	Scarifying Existing road Surface to a Depth of 50 mm by Manual Means, Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	m2	2631.00				
11	Providing and laying granular Sub-Base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means	m3	526.20				
<b>Total</b>							
<b>Total Cost with Ps &amp; Construction</b>							
<b>Vat @ 13% of Total</b>							
<b>Grand Total</b>							

On Behalf of Firm

Signature :  
Name of Firm:  
Seal :  
Name of Authorized Person:  
Permanent Address :  
Phone :  
Date :