



गौरीगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय

फोन नं ४१५०५९-०९९ : ४१५०६०
वेबसाइट: www.gaurigangamun.gov.np
ई : मेल-info.gaurigangamun@gmail.com

प.सं.: २०८२/०८३

च.नं.:



मिति: २०८३/०२/२०

विषय: दररेट पेश
(पटक प्रकासित मिति: २०८३/०२/२०)

यस कार्यालयको देहायका कार्य शिलबन्दी दरभाउपत्र मार्फत सम्पन्न गर्नुपर्ने भएको हुँदा ईच्छुक व्यक्ति/फर्म वा कम्पनी बाट ७ (सात) दिन भित्र दररेट पेश गर्न आव्हान गरिएको छ ।

सि.न.	विवरण	जम्मा रकम (मु.अ.कर सहित) रु.	BOQ खरिद गरि पेश गर्ने अन्तिम मिति र समय
१.	वडा नं ६ को आधारभूत स्वास्थ्य केन्द्रको गेट निर्माण	रु.९७२९९.७७/- (सतानब्वे हजार दुई सय उनानसय पैसा सतहत्तर मात्र)	२०८३/०२/२६ गते कार्यालय समय भित्र
२.	वडा नं.९ जोशीको घर नजिक तटवन्धन निर्माण	रु. १४८४१७.८३/- (एक लाख अरचालिस हजार चार सय सत्र पैसा तिरासी)	

पालना गर्नुपर्ने शर्त तथा पेश गर्नु पर्ने कागजात:-

१. दर्ता भएको ईजाजत प्राप्त निर्माण व्यवसायी/सप्लायर्स भए ईजाजत नविकरण भएको प्रमाण पत्र, मु.अ.कर दर्ता, आ.व. २०८१/०८२ कोकर चुक्ता प्रमाण पत्रको प्रतिलिपि,
२. BOQ यस कार्यालय बाट रु.१००० (एक हजार) मा खरिद गर्नुपर्नेछ । सो खरिद गरेको सक्कल रसिद BOQ साथ पेश गर्नुपर्नेछ ।
३. BOQ शिलबन्दी नभएको दरभाउपत्र दर्ता गरिने छैन ।
४. BOQ मा दररेट अंक र अक्षर दुवैमा लेखिएको/ केरमेट नभएको हुनुपर्नेछ ।
५. म्याद नाघि रित नपुगेको दरभाउपत्र मुल्याङ्कनमा समावेश गरिने छैन ।

ny

२०८३/०२/२०
हरीश पन्त
उपसचिव
उप सचिव
गौरीगङ्गा नगरपालिका

Gauriganga Municipality
Office of Municipal Executive
Chaumala, Kailali
Sudurpaschim Province
Bill of Quantity(BOQ)

Name of Project:- Joshi ji ko ghar najik Tadbandhan Nirman
Location:-Gauriganga 09 Masuriya

F/Y:2082/083

S.N.	Description of Items	Unit	Total Quantity	Rate in figure	Rate in Words	Amount (NRs.)	Remarks
A Civil Works							
1.00	Excavation for Structures Foundation, Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications., Ordinary soil by Mechanical Means,	Cum	9.12				
2.00	Earthwork backfilling with approved material as per Drawing and Technical Specifications.	Cum	8.21				
3.00	Providing and laying mechanical woven Gabion boxes /mattresses, placing in position including stretching; forming compartments; tying the sides and diaphragms with binding wire in each mesh; tying with bracing wires and tie wires, tying down the lid and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, se'vage wire 3.9 mm, lacing wire 2.4 mm)	Cum	30.30				
4.00	Laying and fixing of Geo-Textile all complete as per specification., Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	18.24				
B PROVISIONAL SUMS FOR							
5.00	Off site verification Lab testing of materials as required by the engineer's representative	PS	1.00	5000.00		5000.00	
6.00	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	PS	1.00	1500.00		1500.00	
Sub total amount							
Vat amount(13%)							
Grand total							
IN WORDS:-							
Authorized Signature :-							
Name of form:-							
Deignation:-							
Authorized Name:-							
Office Seal:-							
Date:-							