



गौरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला कैलाली
सुदूरपश्चिम प्रदेश, कैलाली

Bill of Quantity(BOQ)

Name of Project: Malika Ma, Bi Gate Nirman
Location: Gauriganga 02 kailali

S.N.	Description of works	Unit	Quantity	Rate in figure	Rate in words	Total amount	Remark
A	Civil work						
1.00	Dismantling of brick masonry work for wall as per specification and direction of engineer	Cu. m.	1.38				
2.00	Earthwork in excavation for foundation in gravel mixed and silty soils upto the required depth	cum	12.56				
3.00	stone soling work	cum	1.30				
4.00	Providing, laying, compacting and curing plain cement concrete (1:2:4) in foundation with cement, sand and stone ballast 20mm gauge finishing to approved level, lines and dimensions as per the instruction of the site engineer.	cum	1.27				
5.00	P.c.e and R.c.e structural concrete (1:1.5:3 or M20 grade) with cement sand and crushed aggregate in any form, size shape and level for all reinforced cement concrete including mixing, laying, compacting, curing and finishing excluding centering shuttering and cost of reinforcement all complete.	cum	9.60				
6.00	1:4 cement sand mortar with approved quality brick in perfect line & level with necessary scaffolding including wetting the brick, properly packing the joint & curing the with all complete	cum	3.21				
7.00	TOR STEEL WORK: Fixing the steel reinforcement grade 1 conforming to ISI 786-1985 in R.c.c work including cleaning, cutting, bending, placing in position and binding with approved quality bar.	kg	469.01				
8.00	FORMWORK: Supply, fabricate, place and fix wooden formworks with props of any shape for RCC works in Beam including nails, staging/supports, labor, lead & lift at any height, removal and disposal as per approval of engineer.	Sqm	38.97				
9.00	Providing making and fixing sal wood Chaukhat for Main door Door & Windows	cum	0.16				
10.00	32 mm thick ready made compact Door all complete	sqm	1.52				
11.00	38*75mm sal wood frame with 5mm glass all fitting work PLASTERING WORK: Cement sand plastering on walls, ceiling etc. in perfect line and level with top quality finish including necessary scaffolding, raking the joint, wetting the surfaces and curing the plastered surfaces 12.5mm thick cement sand plaster 1:4 on wall inner and outer wall surfaces all complete.	sqm	90.55				
12.00	IRON GATE: Supplying and fixing of Iron channel angle Gate all complete as direction of Site Engineer	kg	261.10				
13.00	PAINTING WORK: Double coat painting work	sqm	90.55				
B.	Electrification						
1.00	Supply and fixing of 42" ceiling fan Aginonard Bajaj or Equi Ns or Is standard . all complete	set	1.00				
2.00	Supply and fixing of LED Bulb 15 W Ns or Is standard all complete	No	6.00				
3.00	Supply and fixing 2x6.0*2.5 sq mm multi strand flexible cu wire for power point in 3/4 " HDPE polythene pipe Ns or Is standard all complete	point	6.00				
	Sub Total						
	Vat Amount @13%						
	Grand Total amount with PS						

On behalf of form:-

Signature:-

Name of form:-

Seal:-

phone:-