



Office of Municipal Executive
Chaumala, Kailali
Bill Of Quantities

Project Name :- Ward Karyalyama Truss, Digital Boardjadan Ra Golghar Bagaicha Nirman
Location :- Gauriganga-02, Kailali

5811012
2021.06
2050192192

SN	Description of Works	Unit	Quantity	Rate (Nrs)		Total Amount(Nrs)	Remarks
				Rate in Figure	Rate in Words		
1	Earth work excavation in foundation and trenches in all type of soil except rock in both dry and wet conditions including back filling of excavated material, shoring and strutting whenever necessary, pumping out water from the trenches etc as directed with the lead of 50 m and lift 3m all complete. Providing and laying Dry-stone soling in foundation work including levelling etc. complete. 150 mm stone soling in foundation	Cum	2.61				
2	Plain cement concrete PCC(1:3:6) in foundation, floors etc. with cement, sand and crushed aggregate of 10 mm to 38mm gauge including mixing with mixture machine & compaction by vibrator, laying in line & level with curing all type of works complete as per specifications & instructions	Cum	6.30				
3	Rubble masonry work including supply of hard stone blocks preparing cement sand mortar and construction of the wall upto 5m high haulage distance upto 10m a) cement sand mortar 1:6 Norms - 6(1-3) page 35	Cum	6.70				
4	20 mm thick Cement sand plaster (1:4) work on building walls surfaces of good finish including racking the joints, wetting the surface and curing the work all complete as per specification	Cum	1.76				
5	Supply, mixing, placing, compact and cure cement sand punning (1:3) over screed in panel, trowel finished including material, labour, curing at any height completed as per drawing, specification and approval of A/E.	Sqm	12.54				
6	MS pipe truss work including cutting, welding, fitting and painting work all complete	Kg	3.23				
7	Sai Wood Work For Bench	cu m	1056.11				
8	1.2 mm Thickness Plain Color Coated Fiber Roofing Sheet, Supplying and fixing of 0.45mm Coloured CGI Sheet Roofing work all complete as per instructions of engineer	Sqm	0.30				
9	Double coat aluminium paint after one coat primer	Sqm	19.59				
10		Sqm	29.24				
11		Sqm	63.30				
Total							
Vat @ 13% of Total							
Grand Total							

On Behalf of Firm,

Signature :

Name of Firm :

Seal :

Name of Authorized Person :

Permanent Address :

Phone :

Date :