



सङ्गणक प्रदर्शन, नेपाल  
BILL OF QUANTITY (BOQ)

Name of Project: **सगर तटस्थान निर्माण**  
Location: **Gauriganga-10, Bhisnur Kailali**  
FY:- 2080/081

सगर तटस्थानको निर्माण  
काठमाडौं, नेपाल  
०१०९  
Date: 2080/08/10  
Signature: [Red Signature]

SN	Description of Works	Unit	Quantity	Rate in Figure	Rate (Nrs)	Rate in Words	Amount (Nrs)
<b>Part 1: Earth Work In Excavation</b>							
1.1	Excavation for Structures Foundation, Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications., Ordinary soil by Mechanical Means, Depth upto 3 m	Cum	143.50				
<b>Part 2: Gabion Works</b>							
2.1	Providing and laying mechanical woven Gabion boxes /mattresses, placing in position including stretching, forming compartments, tying the sides and diaphragms with binding wire in each mesh; Tying with bracing wires and the wires, tying down the lid and filling stone/boulder in gabion boxes/mattress etc. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvaige wire 3.9 mm, lacing wire 2.4 mm)	Cum	162.00				
<b>Part 3: Laying and Fixing of Geo-Textile</b>							
3.1	Laying and fixing of Geo-Textile all complete as per specification., Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	102.50				
<b>Part 4: Earth work in Filling</b>							
4.1	Earth filling in 15 cm layers (N-2-25-Ka) with compaction	Cum	1638				
<b>Part 5: PROVISIONAL SUMS FOR</b>							
5.1	Off site verification Lab testing of materials as required by the engineer's representative	P.S.	1.00	7000			
5.2	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	P.S.	1.00	1500			
			<b>Sub Total</b>				
			<b>Total Construction Cost</b>				
			<b>Vat @ 13% of Total</b>				
			<b>Total Provisional Sum</b>				
			<b>Grand Total</b>				

**Note:**

- The numbers enclosed in the bracket in the particulars represent DOR Standard Specifications Section Number.
- All the specified material acceptance and work compliance tests as per the Standard Specification, 2001 and Quality Assurance Plan (QAP) shall be carried out by the Contractor(s) at his own cost.

**On behalf of contractor**  
Contractor's Signature :  
Firm :  
Contractor's Name :  
Seal :  
Permanent Address :  
Phone :  
Date :

**On behalf of contractor**  
Contractor's Signature :  
Firm :  
Contractor's Name :  
Seal :  
Permanent Address :  
Phone :  
Date :